



These Health & Safety notes identify hazards that were investigated or uncontrolled to mitigate at the design stage. The list is not exhaustive and should not be relied upon. The contractor is to carry out risk assessments and prepare method statements in line with current Health & Safety legislation.

REINFORCED CONCRETE BASEMENT SLAB
Scale 1:50



TYPICAL RIGID BEAM SECTION
Scale 1:20

Health and Safety Notes - General 1 of 2	Suggested Solution/Precaution/Sequence
Pruning of unstable construction	Ensure all props ultimately have a sound foundation.
Pruning of trusses either from structural members	Structural members to be supported prior to removal.
Cladding of any props	No more than one layer of cladding to be supported on props/temporary works at one time.
Building while props/bracing are in place	Structure around area of work should be exposed prior to work commencing, and the commencement of works dependent on the dependencies or poor quality structures.
Inadequate information available prior to commencing work	Adequate means for marking and protecting of elements to be available.
Handling of materials	Carry out in accordance with prepared demolition plan and method statement.
Demolition (through all demolition work are outside scope of work by OSTE)	Restrict access and designate safe zone for demolition.
Deliveries	Contractor to deliver all necessary equipment, temporary propping and support systems prior to demolition and during construction. Ensure all props ultimately removed until new structural forming is complete. Through props should not be removed until new structural forming is complete. Through props should not be removed until new structural forming is complete. Through props should not be removed until new structural forming is complete. Through props should not be removed until new structural forming is complete.
Any scaffolding	Scaffolds to be erected and used in accordance with BS5973. Scaffolds/propping must be inspected and approved before use and at least every 14 days. Ensure they are used in accordance with the manufacturer's instructions.
Clear away rubbish from height/falling debris/dust	All waste materials from height to be deposited via chutes or baskets to ground level steps. Provide building enclosure with adequate temporary dust sheets. Waste removal personnel provided with safe working conditions.
Personnel working at height	Designate safe area for deliveries. Elements to be either dewatered and off-loaded by crane or immediately placed in position (all prep. work to be finished before placement).

Health and Safety Notes - General 2 of 2	Suggested Solution/Precaution/Sequence
These Health & Safety notes identify hazards that were investigated or uncontrolled to mitigate at the design stage. The list is not exhaustive and should not be relied upon. The contractor is to carry out risk assessments and prepare method statements in line with current Health & Safety legislation.	Carry out with extreme care by mechanical means. All elements to be provided with lifting eye/hoists to the designer's requirements.
Excavations	Personal protective equipment to be worn of all workers. No more than one layer of excavation to be supported on props/temporary works at one time.
Excavations	Any damage to steelwork, p.c. units or roof trusses to be repaired or replaced prior to the start of excavation. The contractor is to ensure that the excavation is supported on props/temporary works at one time.
Excavations	Handling and construction to be in accordance with current health and safety legislation and British Standards. The contractor is also to ensure that the excavation is supported on props/temporary works at one time.
Excavations	Site welfare and/or site catering of hot in members is not to be carried out without the Engineer's permission. The Contractor also to ensure that the correct hot specification is used.
Excavations	Adequate warning to excavations is to be provided with all site applications. How steelwork members to be pre-coated prior to delivery.
Excavations	Following the discovery of suspect material, the Contractor is to stop work immediately and report to the Engineer, and seek instructions to proceed (where necessary).

- REINFORCED CONCRETE BASEMENT SLAB AND RETAINING WALLS.**
- THE SETTING OUT OF THE REINFORCED CONCRETE SLAB IN RELATION TO THE RETAINING WALLS IS AS SHOWN ON THE PLAN AND SECTION. THE ENGINEER SHALL BE INFORMED OF ANY VARIATIONS REQUIRED ON SITE PRIOR TO THE START OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FOUNDATION SETTING OUT DETAILS.
 - THE DEPTH TO BOTTOM OF THE LOWER GROUND FLOOR SLAB SHALL CONFORM TO WHICHEVER OF THE FOLLOWING CRITERIA GENERATES THE GREATEST DEPTH:-
 - TO THE MINIMUM DEPTHS AS SHOWN ON THE ENGINEERS DRAWINGS, BELOW EXISTING OR PROPOSED GROUND LEVELS.
 - TO A MINIMUM 500mm BELOW ANY TREE ROOTS EXPOSED DURING EXCAVATIONS, WHERE FOUND IN SHRINKABLE MATERIAL.
 - A MINIMUM OF 300mm INTO UNDISTURBED NATURAL GROUND.
 - FORMATION TO ACHIEVE A MINIMUM BEARING CAPACITY OF 110 kN/m². ANY EXISTING FOUNDATIONS EXCAVATED ARE TO BE GRUBBED OUT LOCALLY AT THE POSITION OF NEW SLAB, TO 300mm BELOW THE DEPTH OF THE EXISTING FOUNDATION LEVEL, AND THE NEW SLAB FORMATION IS TO BE 300mm BELOW THE DEPTH OF THE EXISTING FOUNDATION.
 - ALL EXISTING FOUNDATIONS SHALL BE KEPT FREE FROM WATER, LOOSE MATERIAL AND RUBBISH ETC. THE FORMATION LEVEL SHALL NOT BE EXPOSED UNTIL ALL MADE GROUND, TOPSOIL AND ORGANIC MATTER, TOGETHER WITH ANY SOFT, DISTURBED OR DISCONTIGATED MATERIAL SHOULD BE REMOVED FROM BENEATH THE AREA OF GROUND BEARING SLAB.
 - THE DAY OF THE FORMATION SHOULD BE PROOF ROLLED TO INDICATE ANY FURTHER SOFT SPOTS, WHERE ENCOUNTERED THESE SHOULD BE EXCAVATED AND REPLACED WITH ADDITIONAL GRANULAR FILL.
 - AFTER EXCAVATION TO FORMATION LEVEL, AND REMOVAL OF ALL ROCKETS OF SOFT OR DISTURBED MATERIAL, THE BEARING STRATUM IS TO BE INSPECTED BY THE APPROPRIATE BUILDING CONTROL OFFICER. ONCE APPROVAL OF THE FORMATION HAS BEEN GIVEN, THE CONCRETE SHOULD IDEALLY BE PLACED IMMEDIATELY, HOWEVER, IF THE INTERVAL BETWEEN THE EXCAVATION AND THE PLACING OF THE CONCRETE IS MORE THAN 24 HOURS, THE EXCAVATION SHALL BE FIRST COVERED, THEN THE FORMATION SHOULD BE PROTECTED FROM DEGRADATION BY PLACING A MIN. 50mm THICK LAYER OF CONCRETE BINDING.
 - THE ENGINEER SHOULD BE AFFORDED THE OPPORTUNITY OF INSPECTING THE FORMATION LEVEL UNDER THE SLAB AND REINFORCEMENTS PRIOR TO THE PLACING OF THE CONCRETE. ALLOWED A MINIMUM 24 HOURS NOTICE FOR INSPECTION.
 - SUB BASE TO BE SAND OR CONCRETE BLINDED TO RECEIVE D.P.M. AND/OR WATER-PROOFING.
 - SUB BASE FORMATION SHOULD HAVE A MIN. OF 150mm HOT TYPE 1, WELL GRADED CLEAN INERT GRANULAR MATERIAL, LAYED AND COMPACTED IN MAX. 150mm LAYERS, IN ACCORDANCE WITH TABLE 8/11 OF THE SPECIFICATION FOR HIGHWAY WORKS, FOR LEVELING PURPOSE.
 - THE CONCRETE USED FOR GROUND BEARING SLABS CAN BE SEPARATED FROM THE UNDERLYING FILL MATERIAL BY A DAMP PROOF MEMBRANE (REFER TO ARCHITECTS DRAWINGS FOR SPECIFIC REQUIREMENTS). THE CONCRETE SHALL BE COMPACTED WITH SPECIAL DIGEST 100. ALL CONCRETE IS TO CONFORM TO BS EN 206-1 AND BS 8901-2.
 - REINFORCED CONCRETE
 - ALL CONCRETE WORK IS TO COMPLY WITH THE PROVISIONS OF BS8110 PART 1 THE STRUCTURAL USE OF CONCRETE.
 - ALL STEEL IS TO BE CLEAN AND FREE FROM DELETERIOUS SUBSTANCES, LOOSE RUST OR SCALE, OR ANY COATING THAT WOULD IMPAIR THE BOND.
 - ALL REINFORCEMENT IS TO BE FABRICATED AS DETAILED ON THE BENDING SCHEDULES, CUT AND BENT IN ACCORDANCE WITH BS 4466 AND PROPERLY FIXED IN POSITION WITH ADEQUATE CHAIRS, SPACERS, TYING WIRE ETC TO MAINTAIN THE CONCRETE COVER SPECIFIED.
 - CONCRETE COVER TO REINFORCEMENT TO BE A MINIMUM OF:
 - 35mm FOR BASEMENT SLAB.
 - 35mm FOR RETAINING WALLS.
 - 25mm FOR GROUND FLOOR SLAB & DOWN-STANDING BEAMS.
 - MIN. 40 LENGTHS OF FRESH & LOOSE BARS REINFORCEMENT.
 - 110 - 500MM.
 - 116 - 600MM.
 - 720 - 800MM.
 - 725 - 1000MM.
 - 1232 - 1280MM.
 - CONCRETE STRENGTH/DURABILITY REQUIREMENTS ARE AS FOLLOWS:
 - ALL CONCRETE TO BE GRADE C40 (COMPRESSIVE STRENGTH 40 N/mm²).
 - DESIGN SULPHATE CLASS DS-2 AND APPROPRIATE AECQ CLASS AND DESIGN CHEMICAL CLASS TO B.R.E SPECIAL DIGEST 1.
 - CONCRETE SAMPLING AND TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH BS 1881.
 - THE LAYOUT OF ANY EXISTING DRAINPIPES OR SERVICES IS TO BE CONFIRMED UPON EXCAVATION, AND SHUT SLEEVE DUCTINGS IS TO BE USED WHERE THOSE TO REMAIN, AND ANY NEW DRAINPIPES OR SERVICES TO BE INSTALLED IN ACCORDANCE WITH THE DRAWINGS. ALL SECTIONS SHOULD BE STRIKED SIZES TO REMOVE A MINIMUM 150mm CLEAR VOID AROUND THE PIPE OR SERVICE. THE VOID MAY BE USING EXPANDED POLYSTYRENE OR SIMILAR MATERIAL.
 - THE BASEMENT SLAB SHOULD BE 300MM THICK IN-SITU CONCRETE, REINFORCED THROUGHOUT. IT SHOULD CONSIST OF 2 LAYERS OF B1131 MESH WITH MAIN BARS OF LAYER 1 SPANNING PERPENDICULAR TO MAIN BARS OF LAYER 2, AT TOP & BOTTOM. LAPS IN MESH TO BE 500mm MINIMUM.
 - RETAINING WALLS SHOULD BE 250MM THICK IN-SITU CONCRETE AND REINFORCEMENT SHOULD CONSIST OF B1131 MESH IN EACH FACE WITH MAIN BARS VERTICALLY. FOR FURTHER DETAILS, REFER TO THE GA. SECTIONS AND/OR ELEVATIONS AND BAR BENDING SCHEDULES.
 - THE GROUND FLOOR SLAB TO BE 250MM THICK IN-SITU CONCRETE, REINFORCED THROUGHOUT. IT SHOULD CONSIST OF 1 LAYER OF B1131 MESH (WITH MAIN AS SHOWN ON THE PLAN) AT BOTTOM (MINIMUM OF 50MM LAP) AND 1 LAYER OF A353 MESH AT TOP (MINIMUM OF 40MM MINIMUM).
 - MESH REINFORCEMENT TO BE GRADE 485 TO BS 4483.
 - ALL LOOSE BARS TO BE GRADE 500 H TYPE 2 HOT ROLLED STEEL IN ACCORDANCE TO BS 4449 1997.
 - ALL REINFORCEMENT TO BE FIRMLY HELD IN PLACE.
 - CHAIRS AND SUPPORTS ARE NOT TO SHOW. CONTRACTOR TO PROVIDE SUFFICIENT REINFORCEMENT SUPPORTS AND MAINTAIN COVER TO REINFORCEMENT DURING EXING AND POURING.
 - ALL CONCRETE TO BE FULLY MECHANICALLY VIBRATED.
 - CONCRETE CAST AGAINST BLINDING OR FORMWORK OR SHUTTERS TO HAVE 30mm THICK COVER TO REINFORCEMENT.
 - CONCRETE CAST DIRECTLY AGAINST EARTH TO HAVE 75mm THICK COVER TO REINFORCEMENT.
 - ALL CONCRETE WORK IS TO COMPLY WITH THE ALL CONCRETE MIX CERTIFICATES SHALL BE APPROVED BY THE ENGINEER PRIOR COMMENCEMENT OF WORK ON SITE.
 - SETTLING ONE SET OF 3 CURBS SHALL BE TAKEN FOR EACH 24 HOURS OF CONCRETE PLACED, OR LESS PER DAY. ONE CURB IS TO BE TESTED AT 7 DAYS AND THE REMAINING TWO AT 28 DAYS. 18.
 - FINISHES TO FLOOR SLABS, DPM/DPG, INSULATION ETC TO ARCHITECTS DETAILS.

GENERAL NOTES
THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS BY CISTEC AND DRAWINGS BY ARCHITECTS.
ALL WORKING DIMENSIONS TO BE CHECKED ON SITE.
DO NOT SCALE.
ANY DISCREPANCIES BETWEEN DRAWINGS OF DIFFERENT SCALES AND/OR BETWEEN DRAWINGS AND SPECIFICATION SHALL BE REFERRED TO THE ENGINEER FOR DECISION.
COPYRIGHT RESERVED. THIS DRAWING MAY ONLY BE USED FOR THE CLIENT AND LOCATION SPECIFIED IN THE TITLE BLOCK. IT MAY NOT BE COPIED OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE PRIOR WRITTEN CONSENT OF CISTEC.
PRIOR TO ANY WORK BEING COMMENCED ON SITE, THE ENGINEER SHOULD BE CONTACTED REGARDING THE CURRENT STATUS OR REGULATORY TECHNICAL APPROVAL OF THIS DRAWING.

- BASEMENT FLOOR**
FLOOR CONSTRUCTION TO BE DESIGNED FOR THE FOLLOWING LOADS:
DEAD (EXCLUDING SELF WEIGHT OF FLOOR UNITS);
CHROARD AND INSULATION = 0.15kN/m²
25MM SAND/CHERT SCREENED = 1.0kN/m²
75MM LIGHTWEIGHT STUDCONK - 1.0kN/m²
IMPOSED LOAD (TO BS6399): 1.50 kN/m²

- UPPER FLOORS:**
ALL UPPER FLOORS DESIGNED AND SUPPLIED BY OTHERS.
2. PARTITION WALLS SUPPORTED BY THE FLOORS, REFER TO SPECIALIST PC SUPPLIER AND ARCHITECTS DRAWINGS.

Rev	Amendment	By	Date
P1	Final Issue	JSM	10/07/12
P2	RC Retaining Walls Added	CS7	23/08/13
P3	Typical section of RC Slab added	CS7	01/10/13
A	Revised Section of RC Slab - Insulation To Slab Inside Concrete Slab	CS7	20/11/13
	For Ground Floor		

CISTEC
CONSTRUCTION SERVICES LTD
121, Millon Keynes Business Centre, Farnham Road, Liphord Wood, Nelson Keynes, MK14 6SD, Luton Bedfordshire LU10 9BZ. www.cistec.co.uk
Tel: 01582 500000 Fax: 01582 500001 Email: info@cistec.co.uk

Client: **M Martin Jenkins**

Drawing: **REINFORCED CONCRETE BASEMENT SLAB LAYOUT & DETAILS**

Project: **136 GOLDINGTON ROAD, BEDFORD**

Scale: 1:50 @ A1 Date: 10/07/2012 Approver: JA

Drawing no: **11777 - 301 A**

STATUS: **PRELIMINARY & FOR COMMENTS ONLY**